

## F44 Fore peak ballast system on oil tankers

(June  
2000)  
(Rev.1  
Aug 2008)  
(Rev.2  
Oct 2010)

The fore peak tank can be ballasted with the system serving other ballast tanks within the cargo area, provided:

- The fore peak tank is considered as a hazardous area;
- The vent pipe openings are located on open deck 3 m away at an appropriate distance from sources of ignition. In this respect, the hazardous zones distances are to be defined in accordance to IEC 60092-502: Electrical installations in ships - Tankers - Special features;
- Means are provided, on the open deck, to allow measurement of flammable gas concentrations within the fore peak tank by a suitable portable instrument;
- The sounding arrangement to the fore peak tank is direct from open deck;
- The access to the fore peak tank is direct from open deck. Alternatively, indirect access from the open deck to the fore peak tank through an enclosed space may be accepted provided that:
  1. In case the enclosed space is separated from the cargo tanks by cofferdams, the access is through a gas tight bolted manhole located in the enclosed space and a warning sign is to be provided at the manhole stating that the fore peak tank may only be opened after:
    - it has been proven to be gas free; or
    - any electrical equipment which is not certified safe in the enclosed space is isolated.
  2. In case the enclosed space has a common boundary with the cargo tanks and is therefore a hazardous area, the enclosed space can be well ventilated.

In respect to all paragraphs of this unified requirement, the hazardous area classification is to be defined in accordance to IEC 60092-502: Electrical installations in ships - Tankers - Special features.

---

### Notes:

1. Rev.2 of this UR is to be uniformly implemented by IACS Societies on ships contracted for construction on or after 1 January 2012.
2. The “contracted for construction” date means the date on which the contract to build the vessel is signed between the prospective owner and the shipbuilder. For further details regarding the date of “contract for construction”, refer to IACS Procedural Requirement (PR) No. 29.

End of Document
--------------------